



Clothespin Bridge – Public Informational Meeting

Town of Webster



Town of
Webster New Hampshire
Inc 1860

September 23, 2019

Meeting Agenda

- Introductions and Meeting Purpose
- Review of State Aid Bridge (SAB) Process
- Project Background and Status
- Engineering Study and Design Considerations
- Town Discussion and Input
- Next Steps, Questions, and Wrap-up

Your Project Team



Greg Goodrich, PE
Project Manager



Julie Whitmore, PE
Lead Project Engineer



Peter J. Walker
Permitting Task Lead



Michael Chervincky, PE
Technical QC Engineer



Abbigail Morgan, EIT
Bridge Engineer



Kyle D'Urso, PE
Project Engineer

Meeting Purpose




INTRODUCE PROJECT TO
COMMUNITY




SEEK PUBLIC INPUT

The State Aid Bridge Process





Project Background and Status



Project Location – over Blackwater River



Clothespin Road Bridge – Site Aerial

Project Background – Clothespin Bridge

- Bridge No. 121/103
- Rehabilitated in 1939
- 65-foot long, single span, steel beam bridge with concrete deck
- Condition ratings:
 - Deck = 3 (serious)
 - Superstructure = 5 (fair)
 - Substructure = 4 (poor)
- Currently posted for load (E-2)



Project Background – Clothespin Bridge


- Two-lane Class V road:
 - Approach roadway width = 20-feet
 - Existing bridge width = 18-feet (one lane)
 - Aerial utilities along south side of road
- ADT = 550 VPD (2015)
- **Project Purpose:** To replace this structurally deficient red-list bridge

Project Status

- Environmental Data Collection – Completed
- Topographical Survey – Completed
- Geotechnical Borings – Completed
 - Preliminary Geotechnical Report – Pending
- Engineering Study Phase – Beginning


Engineering Study

- Alternatives Evaluation
 - Roadway Considerations
 - Bridge Considerations
 - Geomorphic Assessment
 - Hydrology and Hydraulics
 - Cost Comparison
 - Local Concerns
- Preferred/Recommended Alternative



Design Considerations – Roadway


- **2015 Truck Routing Study:** highlighted **sight distance** and **horizontal curvature** deficiencies at the bridge
- **Profile modifications** anticipated to accommodate:
 - Structural depth of bridge
 - Required hydraulic opening
 - Permitting requirements
- **Roadway Alignment** Alternative Analysis
 - **On-alignment:** minimize overall impacts and bridge length
 - **Off-alignment:** improvements to sight distance and horizontal curvature




Design Considerations - Roadway

- **Roadway width:**
 - Proposed width to match existing roadway approaches, transitioning to 24-foot bridge section









Clothespin Bridge Road – Alignment, Looking East



On-Line Alternative Simulation




Off-Line Alternative Simulation

Design Considerations – Bridge


- Superstructure types:
 - Steel stringers
 - Precast Concrete Beams (depending on final span length):
 - Butted or spread box beams
 - NEXT Beams
 - Precast NEBT beams
- Substructure Types:
 - Spread footing on rock (west abut.)
 - Stub abutment on piles (east abut.)
 - Integral vs. conventional abutments




Design Considerations – Bridge



Existing Bridge Section




Conceptual Steel Section




Conceptual Concrete Section

Design Considerations – Bridge


- Hydraulic study considerations:
 - HEC-RAS analysis
 - 1-foot of freeboard to Q50 storm
 - Evaluation of Q100 storm to maintain WS elevs.
- FEMA study (by detailed methods)
- Scour analysis for Q100 and Q500
- Stream crossing rules will also influence span length



Design Considerations – Bridge



Conceptual Bridge Elevation



Traffic Management During Construction – Detour (4.6 mi)

Design Considerations – Bridge

- Accelerated Bridge Construction (ABC) considerations
 - Full ABC not recommended:
 - Short detour
 - Low ADT
 - Cost considerations
 - Select details can be used to:
 - Reduce construction duration
 - Minimize impacts to residents




Design Considerations – Bridge

- ABC component considerations:
 - Prefabricated elements (i.e. precast, etc.)
 - Limit closure activities
 - Schedule requirements



Town Input

- Local Concerns?
 - Emergency Routes
 - School Bus Routes
 - Flooding
 - Events
 - Construction start/end
- Bridge Committee



Next Steps

- Develop Engineering Study (first deliverable)
- 2nd Public Informational Meeting – date TBD
- Permitting and Final Design
- Construction - 2024





Questions/Comments??